



TYPICAL 1500 GALLON TANK
SEPTIC TANK SIDE VIEW
NO SCALE

- NOTES:
1. TANK MANUFACTURER MUST BE APPROVED BY THE OREGON DEQ AND BE MARKED WITH THE MANUFACTURER'S DEQ REGISTRATION NUMBER AND TANK CAPACITY.
 2. OUTLET PIPE INVERT SHALL BE 3" LOWER THAN THE INLET PIPE INVERT.
 3. TANK SHALL BE TESTED FOR LEAKS BY FILLING WITH WATER FOR 24 HOURS. THE MAXIMUM ALLOWABLE LEAKAGE IS 1 GALLON OVER 24 HOURS.
 4. MAXIMUM COVER OVER TANK IS 36". FOR DEPTHS GREATER THAN THIS THE MANUFACTURER MUST PROVIDE AN ENGINEERED STRUCTURAL ANALYSIS DEMONSTRATING THAT THE TANK CAN WITHSTAND THE HIGHER SOIL LOADS.