

SUPPLEMENTAL SPECIFICATIONS

Public Works Construction done on facilities managed by Rogue Valley Sewer Services shall be constructed in accordance with the 2008 edition of the “Standard Specifications for Public Works Construction” ODOT/APWA as modified by the following supplemental specifications. Number references in these Supplemental Specifications shall be understood to refer to the Sections and Subsections of the Standard Specifications bearing like numbers and to Sections and Subsections contained herein in their entirety.

Contractors are expected to have a copy of the Standard Specifications on the Project Site. Standard Specifications may be obtained from the ODOT Contractor Plans office, Room 28 Transportation Building, 355 Capitol St. NE, Salem, Oregon 97301.

When there are differences or conflicts between the specifications, Supplemental Drawings, or standard details, the conflict shall be resolved as follows:

1. Permit requirements.
2. Supplemental Drawings specific to the work.
3. Special Provisions
4. Supplemental Specifications
5. Standard Specifications
6. Standard Drawings

Measurement and Payment provisions of the Standard Specifications are not part of this Contract. The measurement and payment of bid items will be included in the Special Provisions. Items of work not included in the Special Provisions will be considered incidental to the project and no separate payment will be made, except as allowed under the Change Order provisions of the Standard Specifications.

Unanticipated Rock Excavation: In the event that unanticipated rock excavation is encountered, the unit price for same is hereby pre-established at One Hundred Dollars (\$100) per cubic yard as measured in place prior to disturbance. If 20 per cent or more rock is encountered than included in the bid item, rock in excess of the bid item shall be considered unanticipated and paid at the dollar amount above. By submittal of a Bid for the project, Bidders acknowledge the sufficiency of the above unit price for unanticipated rock excavation.

Hours of Work: Normal working hours for this project are between 7:00 am and 6:00 pm, Monday through Friday, excluding Federal holidays. The Contractor may work outside of these hours only with prior approval by Rogue Valley Sewer Services. Contractor agrees to pay any overtime costs incurred by RVS resulting from work done outside of normal working hours.

00110.20 Definitions: The term “Agency” refers to Rogue Valley Sewer Services (RVS)

00110.31 Use of Metric or Customary (“English”) System: Supplemental Drawings may be in either metric or English units, at the discretion of the Engineer. Work must be done in the units shown on the Supplemental Drawings.

00120.00 Prequalification of Bidders: Contractor pre-qualification is valid for two years. Contractor must be pre-qualified at the time of bid closing to have a bid considered for the project.

00120.05 Requests for Solicitation Documents: Bidders must obtain Solicitation Documents from the Rogue Valley Sewer Services office at 138 West Vilas Road, Central Point, OR 97502.

Each request for documents must include the bidders contact phone number and fax number.

00120.40 (f) Disclosure of First-Tier Subcontractors: Disclosures will not be accepted via Email.

00120.45 Submittal of Bids: Bids must be received by the Bid Closing time at the RVS office at 138 West Vilas Road, Central Point, OR.

00120.60 Revisions or Withdrawal of Bids: Changes to bid must be received by the time of the Bid Closing at the RVS office at 138 West Vilas Road, Central Point, OR.

00180.33 Metric Submittals: The contractor shall use the same unit system as shown on the Supplemental Drawings for measurements and calculations.

00185.85 (b) Liquidated Damages: Liquidated damages shall be assessed as described in Part 1 – Bidding Requirements.

00195.50(a)(1) Progress Estimates: Progress estimates shall include work done through the last day of each month.

00195.50(c) Forms of Retainage: The only form of retainage shall be Cash, Alternate A.

00159.50(e) Withholding Payments: Retainage shall be increased to 25% if the Contractor fails to provide complete and accurate payroll statements.

00405.13 Pipe Zone Material: Pipe zone material for rigid pipe material shall meet the specifications defined in 02630.10 or 02630.11 as specified by RVSS.

00445.11 Materials: Unless otherwise specified, sanitary sewer pipe shall be PVC conforming to ASTM D-3034 with a minimum SDR of 35.

00445.11(g) Repair Clamps: Repair clamps shall be made using an approved rigid coupler, Romac 501 or approved equal. Flexible couplers are not allowed on sewer main lines or service lines within the Right of Way.

00445.48 Tracer Wire: Tracer wire is required on service line pipe and on curved main line sewers. It is not required on main line sewers which run in a straight line between manholes or from a manhole to a cleanout.

00445.74 Television Inspection of Sanitary and Storm Sewers: Television inspections will be performed by RVS Staff.

00470.45 Steps and Ladders: Manholes shall not have steps or ladders attached to the manhole walls.